Abstract of estimate for constructing Sheristedar's Quarters at Bagepalli.

Sl. No.	Items of work	Unit	Quantity.
1	Earthwork excavating foundations and filling in basement ..	C.yd.	84
2	Chunam concrete with burnt stone jelly	C.ft.	684
3	Burnt stone in clay for foundations and basement ...	,,	1,964
4	Burnt brick in clay	,,	2,234
5	Burnt brick in chunam	,,	536
6	Burnt stone slab 6" thick dressed	S.ft.	420
7	Chunam plastering	Sqr.	60·00
8	White washing two coats	,,	60·00
9	Teakwood battened doors with hinges bolts, etc., complete ...	S.ft.	222
10	Teakwood battened windows with iron bars, hinges, hooks, etc., complete.	,,	55
11	Teakwood ventilators with iron bars, hinges, etc., complete ...	,,	60
12	Teakwood wrought and put up complete	C.ft.	84
13	Rolled steel joints 3" x 6" including putting charges painting complete.	,,	4
14	Roofing with 1st class Mangalore tiles on teak reepers with nails, etc., complete.	Sqr.	17·35
15	Terrace with jack arches	,,	1·09
16	Burnt brick coping with plastering with chunam, etc., complete	R.ft.	55
17	Flooring with 1st class Mangalore tiles on 3" concrete bedding with cement pointing.	Sqr.	5·30
18	Flooring with burnt stone slabs 3" thick one line dressed on 3" concrete bedding with cement pointing.	,,	2·84
19	Cement pointing	,,	3·59
20	Wood oiling to wood work	,,	8·00
21	Chocolate silicate pointing 3 coats	,,	6·13
22	Parapet wall 1½' x 1½'	R.ft.	27
23	Cornice 9" thick	,,	30
24	Tarring	Sqr.	5·00
25	Chunam borders 9" thick	R.ft.	77
26	Providing valley with zinc sheets teak planks and finished with cement.	,,	11
27	Ridge tiles set in mortar	,,	115
28	Construction of seats in the latrine and providing drain pipes and also providing sinks in the bath and kitchen.	L. S.	
29	Site clearing levelling ground and unforeseen	L. S.	
30	Mortar and pestle	L. S.	

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

MYSORE DIVISION.

Dated 3rd March 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 3 P.M., on 9th April 1930 for restoring Raghavapur Tank Registered No. 4 of Gundlupet Taluk, Mysore District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1932.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore Division between the hours of 11 A.M. and 5 P.M., on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 1,000 (one thousand only) cash or Government Promissory Notes, as earnest money, and be superscribed "tender restoring Raghavapur Tank, Regd. No. 4 of Gundlupet Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond in default of which his tender will be cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. Rates should be quoted for each item of work.

Abstract estimate for Restoring Raghavapur Major Tank, Regd. No. 4, Gundlupet Taluk, Mysore District.

No.	Items of work	Unit	Quantity	Rate	Cost
	A. Bund.			Rs.	Rs.
1	Clearing jungle and trees thirty years ...	Acres	17½		
2	Cutting grass on old ...	"	43		
3	Earthwork to bund including watering and stamping with lead ...	C. Yds.	5,861		
4	New stone revetment ...	"	879		
5	Gravel to top of bund including carting and consolidating.	"	272		
6	Turfing including carting ...	"	1,219		
7	Removing and refixing old rude stones including carving figures, painting and numbering	No.	20		
8	Preparing and fixing new rude stones with bolts in place of missing ones, including carving figures painting and numbering, etc.	"	28		
9	Preparing and fixing vent stone ...	"	48		
10	Preparing and fixing B. M. stones including carving figures numbering and painting ...	"	2		
11	Preparing and fixing datum and Reg. No. stone including carving figures, painting and numbering, etc.	"	2		
12	Preparing and fixing gauge stone including carving figures, painting and numbering, etc.	Lump sum		Rs.	
13	Resetting revetment (old) ...	Lump sum		Rs.	
	B. Breach Cutting No. I.				
1	Excavating and removing earth silt and sand in breach.	Cyds.	723		
2	Earth work excavating inside trench and foundation of revetment and ramp to bund.	"	103		
3	Puddle wall with gravel and clay ...	"	429		
4	Earth work to breach including watering and stamping with lead and lift excluding quantity of puddle, revetment and gravel backing.	"	5,164		

No.	Items of work	Per	Quantity	Rate	Cost
5	Gravel backing to revetment	C.yds.	125	Rs.	
6	New stone work for breach portion ...	"	372		
7	Turfing including carting, etc.	Sqr.	68·60		
8	Jelly and transverse drains	Lump	sum		
	III. Breach Filling No. 2.				
1	Earthwork and removing silt and sand in breach.	C.yd.	4,665		
2	Excavating soft rock and earth for foundation of revetment dwarff wall core walls and puddle wall.	"	317		
(a)	Benching rock	S.ft.	200		
3	Burnt brick in surki mortar for dwarf wall ...	C.ft.	1,350		
4	New stone work with jelly	C.yd.	11		
5	Puddle wall with gravel and clay	"	1,212		
6	Earthwork to breach including watering and tamping with lead and lift excluding quantity of puddle revetment and gravel backing.	"	9,439		
7	Gravel backing to revetment	"	460		
8	New stone work for revetment	"	1,173		
9	Turfing including carting, etc.	Sqr.	137·68		
	IV. Sluice.				
1	Earthwork cutting bund	C.yd.	217		
2	Dismantling and removing revetment ...	"	7		
3	Earthwork excavation	"	34		
4	Concrete in surki mortar	C.ft.	562		
5	Burnt brick in surki mortar	"	833		
6	Burnt stone slabs dressed and fixed (6") ...	S.ft.	299		
7	Cutting hole in the slab orifice and guide slab ...	No.	4		
8	Cement plastering ½" thick	Sqr.	0·69		
9	Cement pointing	"	2·17		
10	Surki mortar plastering	"	6·28		
11	Providing teakwood plug and rod with locking arrangement, etc.	Lump	sum		
12	Filling earth with watering and tamping ...	C.yd.	112		
13	Gravel backing behind revetments to existing bund.	"	3		
14	Resetting old stone work with new jelly to existing bund.	"	7		
15	Turfing	Sqr.	1·98		
	V. Repairing the existing sluices.				
1	Providing plug and rod with locking arrangements and patch repairs to masonry, etc.	No.	2		
	VI. Extending the Right weir.				
1	Excavating soft rock mixed with earth ...	C.yd.	2,576		
2	Concrete in surki mortar	C.ft.	150		
3	Burnt brick in surki mortar	"	296		
4	Burnt stone slabs dressed and fixed with pointing.	S.ft.	202		
5	Surki mortar plastering	Sqr.	0·50		
6	New stone work	C.yd.	19		
	VII. Repairing the existing Right weir.				
1	Excavating soft rock	C.yd.	51		
2	Burnt brick in surki mortar	C.ft.	127		
3	Burnt stone slab dressed and fixed with pointing	S.ft.	101		
4	Surki mortar plastering	Sqr.	0·50		
5	Jelly wedging to existing apron and patch repairs to masonry.	Lump	sum		
6	New stone work	C.yd.	45		